

Town of Andover, NH
HIGHWAY DEPARTMENT GARAGE PROJECT
ADDENDUM No. 3

1. **Location of Wash Bay.** The location of the wash bay shall be considered during the development of conceptual designs and as a part of the submission process. Locating the wash bay next to the office area is an acceptable alternative.
2. **Cold Storage Bays.** The alternate design with two bays of cold storage is envisioned as being fully open on the garage door side and enclosed on three sides along the side, back and the adjoining wash bay wall.
3. **Section 1.5 R-values.** The R values indicated in section 1.5 are minimum values and are acceptable for this project.
4. **Performance Requirements.** Testing requirements are those that are required by the engineer of record to meet code.
5. **Alternative Bay Heating.** Radiant floor heating is required for submission packages. Submitting firms may offer alternatives to this system as an additional information or qualifications and assumptions page with the submission.
6. **Ventilation and Cooling Systems.** Ventilation should meet IBC and ASHRAE standards for the office space, break room and toileting facilities. Additionally the cost for a split-system heat pump covering these areas should be included in the design package.

End of Addendum 3